

Houston Automotive Group

Texas Truck Center

10555 F.M. 1960
Houston, TX 77070
Phone (281) 807-6500 Fax (281) 807-5300



Attn:

DATE: 6/22/2009

Quotation For:

Quotation valid until: 7/22/2009
Prepared by:

SALESPERSON	P.O. NUMBER	START DATE	FINISH DATE	F.O.B. POINT	TERMS
				Houston	

Qty	Part #	Equipment	Amount
		<p>WORK ORDER #: 18 / QUOTE #: 862372-4</p> <p>Length: 168" plus header or OR Deck Width: 96" O A Width: 100 1/2" 1/8" tread plate deck 4" structural channel long sills with gussets on every cross member and 6-channel braces. 4" x 2" x 1/4" rear cross members Formed 4" x 3/16" front cross members on 12" centers Longitudinal wheel well floor support structure 3/8" formed rear torsion sub frame 3/16" formed front torsion sub frame (Extends to front of WW area) 1/2" crane plate reinforced with 1/2" x 4" x 3 1/2" structural angle 8 external stake pockets on each side of platform. 2 1/2" x 3/8" rub rails. Tubing header welded forward of platform. Header has 12 gauge kick panel and 1 1/2 x #9 expanded metal in window area. Full skirted tail section Spring retract manual outriggers. Crane side extends 34". 18" step bumper with receiver hitch. 1 - 18T x 18D x 82L Dutec toolbox is mounted UB on each side at the front of the body. 1 - 18T x 18D x 36L Dutec toolbox is mounted UB on LH rear side of the body. 1 - 22T x 22D x Crane box inset in RH rear side of platform. Crane plate is flush with platform deck. A wheel well panel connects front and rear toolboxes. Factory wired and lighted Epoxy Primer and white acrylic enamel gloss white top coat</p>	
		<p>Please show acceptance by signing below and faxing back to me at (281) 807-6444.</p> <p>Order Acknowledgement / Authorization:</p> <hr/> <p>By:</p>	

THANK YOU FOR YOUR BUSINESS!

SUBTOTAL	\$0.00
TAX RATE	7.25%
SALES TAX	-
TOTAL	\$ -